

RUNDSTAHL - STÜCKLISTE B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Sohle Entwässerungsgebäude - untere Lage

Plannr.: B13-01

Datum: 03.04.2024

POS.	STÜCK	ø (mm)	SCHNITTLÄNGE (m)	GEWICHT (kg)	GESAMTLÄNGE (m)
1	41	16	5,800	9,164	237,800
2	41	16	5,200	8,216	213,200
3	117	16	3,750	5,925	438,750
4	118	16	10,150	16,037	1.197,700
5	1	16	8,700	13,746	8,700
6	2	16	9,300	14,694	18,600
7	1	16	9,550	15,089	9,550
8	2	16	3,200	5,056	6,400
9	2	16	2,900	4,582	5,800
10	10	16	11,200	17,696	112,000
11	107	16	11,650	18,407	1.246,550
12	3	16	9,900	15,642	29,700
13	3	16	10,250	16,195	30,750
14	3	16	3,100	4,898	9,300
15	107	16	6,600	10,428	706,200
16	15	16	4,850	7,663	72,750
17	3	16	2,650	4,187	7,950
18	20	16	3,450	5,451	69,000
19	94	16	3,240	5,119	304,560
20	446	16	2,690	4,250	1.199,740
21	22	16	1,750	2,765	38,500
22	2	16	2,320	3,666	4,640
23	2	14	2,300	2,783	4,600
24	1	16	2,280	3,602	2,280
25	5	16	1,550	2,449	7,750
26	10	16	1,230	1,943	12,300
27	3	16	1,880	2,970	5,640
28	4	16	2,380	3,760	9,520
29	6	14	1,750	2,117	10,500
30	2	14	1,850	2,239	3,700
31	2	16	1,200	1,896	2,400
32	243	16	2,650	4,187	643,950
33	14	14	1,550	1,875	21,700
34	3	16	1,660	2,623	4,980
35	2	16	2,600	4,108	5,200
36	8	16	1,790	2,828	14,320
37	3	16	3,280	5,182	9,840
38	3	16	2,300	3,634	6,900
39	21	14	1,650	1,997	34,650
40	20	16	5,000	7,900	100,000
41	3	16	2,950	4,661	8,850
42	51	16	2,150	3,397	109,650
43	10	16	1,850	2,923	18,500
44	16	16	3,450	5,451	55,200

(Alle Angaben gerundet!)

Fortsetzung Seite 2

RUNDSTAHL - STÜCKLISTE B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Sohle Entwässerungsgebäude - untere Lage

Plannr.: B13-01

Datum: 03.04.2024

POS.	STÜCK	ø (mm)	SCHNITTLÄNGE (m)	GEWICHT (kg)	GESAMTLÄNGE (m)
45	43	16	3,240	5,119	139,320
46	14	16	3,160	4,993	44,240
47	112	16	2,350	3,713	263,200
48	112	16	3,150	4,977	352,800
49	112	16	1,540	2,433	172,480
GESAMTMENGE (BETONSTAHL B500)					
	(mm)	(kg/m)		(m)	(kg)
14		1,210		75,150	90,932
16		1,580		7.957,460	12.572,786
GESAMTGEWICHT					12.663,718

(Alle Angaben gerundet!)

BIEGELISTE Stabstahl B500





















Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Sohle Entwässerungsgebäude - untere Lage

Plannr.: B13-01

Datum: 03.04.2024

Pos.	Skizze [m/cm]	Stück	Ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
1		41	16	5,80	237,80	375,724
2		41	16	5,20	213,20	336,856
3		117	16	3,75	438,75	693,225
4		118	16	10,15	1.197,70	1.892,366
5		1	16	8,70	8,70	13,746
6		2	16	9,30	18,60	29,388
7		1	16	9,55	9,55	15,089
8		2	16	3,20	6,40	10,112
9		2	16	2,90	5,80	9,164
10		10	16	11,20	112,00	176,960
11		107	16	11,65	1.246,55	1.969,549
12		3	16	9,90	29,70	46,926
13		3	16	10,25	30,75	48,585
14		3	16	3,10	9,30	14,694
15		107	16	6,60	706,20	1.115,796
16		15	16	4,85	72,75	114,945
17		3	16	2,65	7,95	12,561
18		20	16	3,45	69,00	109,020
19		94	16	3,24	304,56	481,205
20		446	16	2,69	1.199,74	1.895,589

(Alle Angaben gerundet!)

Fortsetzung Seite 4

BIEGELISTE Stabstahl B500











Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Sohle Entwässerungsgebäude - untere Lage

Plannr.: B13-01

Datum: 03.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
21		22	16	1,75	38,50	60,830
22		2	16	2,32	4,64	7,331
23		2	14	2,30	4,60	5,566
24		1	16	2,28	2,28	3,602
25		5	16	1,55	7,75	12,245
26		10	16	1,23	12,30	19,434
27		3	16	1,88	5,64	8,911
28		4	16	2,38	9,52	15,042
29		6	14	1,75	10,50	12,705
30		2	14	1,85	3,70	4,477

BIEGELISTE Stabstahl B500












Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Sohle Entwässerungsgebäude - untere Lage

Plannr.: B13-01

Datum: 03.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
31		2	16	1,20	2,40	3,792
32		243	16	2,65	643,95	1.017,441
33		14	14	1,55	21,70	26,257
34		3	16	1,66	4,98	7,868
35		2	16	2,60	5,20	8,216
36		8	16	1,79	14,32	22,626
37		3	16	3,28	9,84	15,547
38		3	16	2,30	6,90	10,902
39		21	14	1,65	34,65	41,927
40		20	16	5,00	100,00	158,000
41		3	16	2,95	8,85	13,983

BIEGELISTE Stabstahl B500









Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Sohle Entwässerungsgebäude - untere Lage

Plannr.: B13-01

Datum: 03.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
42		51	16	2,15	109,65	173,247
43		10	16	1,85	18,50	29,230
44		16	16	3,45	55,20	87,216
45		43	16	3,24	139,32	220,126
46		14	16	3,16	44,24	69,899
47		112	16	2,35	263,20	415,856
48		112	16	3,15	352,80	557,424
49		112	16	1,54	172,48	272,518