

RUNDSTAHL - STÜCKLISTE B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

POS.	STÜCK	ø (mm)	SCHNITTLÄNGE (m)	GEWICHT (kg)	GESAMTLÄNGE (m)
1	1	20	5,050	12,474	5,050
2	8	8	1,260	0,498	10,080
3	2	20	7,000	17,290	14,000
4	6	20	7,300	18,031	43,800
5	4	8	1,780	0,703	7,120
6	2	20	6,550	16,179	13,100
7	2	20	6,800	16,796	13,600
8	8	8	1,105	0,436	8,840
9	4	16	8,950	14,141	35,800
10	3	16	8,600	13,588	25,800
11	3	16	10,750	16,985	32,250
12	4	16	11,000	17,380	44,000
13	7	16	6,400	10,112	44,800
14	1	16	5,150	8,137	5,150
15	3	16	6,550	10,349	19,650
16	43	20	2,250	5,558	96,750
17	1	16	3,600	5,688	3,600
18	51	16	2,100	3,318	107,100
19	1	16	2,500	3,950	2,500
20	3	16	3,650	5,767	10,950
21	11	16	4,200	6,636	46,200
22	7	16	3,500	5,530	24,500
23	7	20	3,700	9,139	25,900
24	7	20	6,850	16,920	47,950
25	8	12	1,700	1,510	13,600
26	1	20	4,050	10,004	4,050
27	8	12	2,250	1,998	18,000
28	1	16	3,150	4,977	3,150
29	12	20	6,350	15,685	76,200
30	12	20	4,100	10,127	49,200
31	10	16	4,650	7,347	46,500
32	8	25	8,405	32,359	67,240
33	1	16	8,800	13,904	8,800
34	6	20	4,150	10,251	24,900
35	6	20	5,200	12,844	31,200
36	6	20	6,350	15,685	38,100
37	4	16	4,150	6,557	16,600
38	5	16	4,950	7,821	24,750
39	3	16	6,000	9,480	18,000
40	1	16	4,250	6,715	4,250
41	1	16	5,050	7,979	5,050
42	16	20	2,900	7,163	46,400
43	5	10	2,320	1,431	11,600
44	5	10	1,820	1,123	9,100

(Alle Angaben gerundet!)

Fortsetzung Seite 2

RUNDSTAHL - STÜCKLISTE B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

POS.	STÜCK	ø (mm)	SCHNITTLÄNGE (m)	GEWICHT (kg)	GESAMTLÄNGE (m)
45	2	12	1,310	1,163	2,620
46	4	12	1,310	1,163	5,240
47	8	12	0,900	0,799	7,200
48	6	12	1,100	0,977	6,600
49	8	12	1,200	1,066	9,600
50	8	12	1,850	1,643	14,800
51	48	12	1,700	1,510	81,600
52	39	8	1,460	0,577	56,940
53	1	8	2,560	1,011	2,560
54	1	8	1,340	0,529	1,340
55	1	8	1,420	0,561	1,420
56	29	10	3,340	2,061	96,860
57	5	8	1,360	0,537	6,800
58	2	8	2,320	0,916	4,640
59	3	8	2,000	0,790	6,000
60	3	8	2,260	0,893	6,780
61	3	8	2,020	0,798	6,060
62	2	8	2,080	0,822	4,160
63	3	8	1,760	0,695	5,280
64	3	8	1,240	0,490	3,720
65	2	8	1,260	0,498	2,520
66	6	8	1,580	0,624	9,480
67	4	16	6,400	10,112	25,600
68	4	16	11,650	18,407	46,600
69	1	16	10,650	16,827	10,650
70	10	25	10,850	41,773	108,500
71	5	25	8,405	32,359	42,025
72	1	16	3,500	5,530	3,500
73	1	16	4,850	7,663	4,850
74	6	16	7,100	11,218	42,600
75	6	25	12,000	46,200	72,000
76	4	16	7,200	11,376	28,800
77	7	20	8,600	21,242	60,200
78	4	16	4,150	6,557	16,600
79	1	16	7,400	11,692	7,400
80	12	12	1,300	1,154	15,600
81	136	12	2,100	1,865	285,600
82	262	10	1,100	0,679	288,200
83	24	8	0,880	0,348	21,120
84	60	20	3,100	7,657	186,000
85	14	16	1,600	2,528	22,400
86	3	16	10,050	15,879	30,150
87	4	16	8,450	13,351	33,800
88	1	16	6,600	10,428	6,600

(Alle Angaben gerundet!)

Fortsetzung Seite 3

RUNDSTAHL - STÜCKLISTE B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

POS.	STÜCK	ø (mm)	SCHNITTLÄNGE (m)	GEWICHT (kg)	GESAMTLÄNGE (m)
89	6	20	8,405	20,760	50,430
90	7	20	12,000	29,640	84,000
91	1	16	11,250	17,775	11,250
92	1	16	7,500	11,850	7,500
93	1	16	10,400	16,432	10,400
94	3	16	6,900	10,902	20,700
95	6	25	7,210	27,759	43,260
96	6	25	12,000	46,200	72,000
97	10	25	3,500	13,475	35,000
98	4	8	1,900	0,750	7,600
99	2	8	2,080	0,822	4,160
100	1	8	1,460	0,577	1,460
101	1	8	1,380	0,545	1,380
102	2	8	1,440	0,569	2,880
103	166	10	2,920	1,802	484,720
104	58	10	3,120	1,925	180,960
105	28	10	2,880	1,777	80,640
106	57	10	3,080	1,900	175,560
107	10	8	1,760	0,695	17,600
108	4	16	2,130	3,365	8,520
109	2	16	2,460	3,887	4,920
110	2	8	1,550	0,612	3,100
111	2	8	1,840	0,727	3,680
112	2	8	1,880	0,743	3,760
113	2	8	1,680	0,664	3,360
114	2	8	1,820	0,719	3,640
115	3	16	2,260	3,571	6,780
116	6	16	2,050	3,239	12,300
117	160	8	1,750	0,691	280,000
118	1	8	1.760,000*	695,200	1.760,000
119	6	20	2,830	6,990	16,980
120	3	20	2,900	7,163	8,700
121	9	25	3,430	13,206	30,870
122	1	8	2,020	0,798	2,020
123	1	8	1,920	0,758	1,920
124	1	8	1,520	0,600	1,520
125	72	8	3,380	1,335	243,360
126	88	10	3,160	1,950	278,080
127	99	8	3,340	1,319	330,660
128	28	8	3,120	1,232	87,360
129	48	12	3,400	3,019	163,200
130	3	12	3,220	2,859	9,660
131	48	12	2,980	2,646	143,040
132	8	10	3,160	1,950	25,280

(Alle Angaben gerundet!)

Fortsetzung Seite 4

RUNDSTAHL - STÜCKLISTE B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

POS.	STÜCK	ø (mm)	SCHNITTLÄNGE (m)	GEWICHT (kg)	GESAMTLÄNGE (m)
133	13	8	2,840	1,122	36,920
134	13	8	3,040	1,201	39,520
135	6	12	2,960	2,628	17,760
136	6	10	2,120	1,308	12,720
137	13	10	1,880	1,160	24,440
138	13	10	1,400	0,864	18,200
139	7	10	2,080	1,283	14,560
140	7	10	1,360	0,839	9,520
141	4	16	1,970	3,113	7,880
142	4	8	1,960	0,774	7,840
143	8	10	3,380	2,085	27,040
144	7	10	1,100	0,679	7,700
145	7	10	2,040	1,259	14,280
146	7	10	2,340	1,444	16,380
147	1	8	2,280	0,901	2,280
148	102	8	3,300	1,304	336,600
149	135	8	2,880	1,138	388,800
150	102	8	3,080	1,217	314,160
151	6	16	2,160	3,413	12,960
152	2	16	2,210	3,492	4,420
153	5	8	1,610	0,636	8,050
154	1	8	1,470	0,581	1,470
155	16	12	3,150	2,797	50,400
156	14	10	1,510	0,932	21,140
157	14	10	1,590	0,981	22,260
158	30	8	2,000	0,790	60,000

GESAMTMENGE (BETONSTAHL B500)

(mm)	(kg/m)	(m)	(kg)
8	0,395	4.119,960	1.627,384
10	0,617	1.819,240	1.122,470
12	0,888	844,520	749,936
16	1,580	916,580	1.448,197
20	2,470	936,510	2.313,182
25	3,850	470,895	1.812,946

GESAMTGEWICHT

9.074,115

* laufende Meter
(Alle Angaben gerundet!)

BIEGELISTE Stabstahl B500















Projekt: Zentralklärwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
1		1	20	5,05	5,05	12,474
2		8	8	1,26	10,08	3,982
3		2	20	7,00	14,00	34,580
4		6	20	7,30	43,80	108,186
5		4	8	1,78	7,12	2,812
6		2	20	6,55	13,10	32,357
7		2	20	6,80	13,60	33,592
8		8	8	1,105	8,84	3,492
9		4	16	8,95	35,80	56,564
10		3	16	8,60	25,80	40,764
11		3	16	10,75	32,25	50,955
12		4	16	11,00	44,00	69,520
13		7	16	6,40	44,80	70,784
14		1	16	5,15	5,15	8,137

BIEGELISTE Stabstahl B500

Projekt: Zentralklärwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
15		3	16	6,55	19,65	31,047
16		43	20	2,25	96,75	238,973
17		1	16	3,60	3,60	5,688
18		51	16	2,10	107,10	169,218
19		1	16	2,50	2,50	3,950
20		3	16	3,65	10,95	17,301
21		11	16	4,20	46,20	72,996
22		7	16	3,50	24,50	38,710
23		7	20	3,70	25,90	63,973
24		7	20	6,85	47,95	118,437
25		8	12	1,70	13,60	12,077

BIEGELISTE Stabstahl B500















Projekt: Zentralklärwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
26		1	20	4,05	4,05	10,004
27		8	12	2,25	18,00	15,984
28		1	16	3,15	3,15	4,977
29		12	20	6,35	76,20	188,214
30		12	20	4,10	49,20	121,524
31		10	16	4,65	46,50	73,470
32		8	25	8,405	67,24	258,874
33		1	16	8,80	8,80	13,904
34		6	20	4,15	24,90	61,503
35		6	20	5,20	31,20	77,064
36		6	20	6,35	38,10	94,107
37		4	16	4,15	16,60	26,228
38		5	16	4,95	24,75	39,105
39		3	16	6,00	18,00	28,440

BIEGELISTE Stabstahl B500













Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
40		1	16	4,25	4,25	6,715
41		1	16	5,05	5,05	7,979
42		16	20	2,90	46,40	114,608
43		5	10	2,32	11,60	7,157
44		5	10	1,82	9,10	5,615
45		2	12	1,31	2,62	2,327
46		4	12	1,31	5,24	4,653
47		8	12	0,90	7,20	6,394
48		6	12	1,10	6,60	5,861
49		8	12	1,20	9,60	8,525
50		8	12	1,85	14,80	13,142
51		48	12	1,70	81,60	72,461

BIEGELISTE Stabstahl B500










Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plan nr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	Ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
52		39	8	1,46	56,94	22,491
53		1	8	2,56	2,56	1,011
54		1	8	1,34	1,34	0,529
55		1	8	1,42	1,42	0,561
56		29	10	3,34	96,86	59,763
57		5	8	1,36	6,80	2,686
58		2	8	2,32	4,64	1,833
59		3	8	2,00	6,00	2,370
60		3	8	2,26	6,78	2,678

BIEGELISTE Stabstahl B500












Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
61		3	8	2,02	6,06	2,394
62		2	8	2,08	4,16	1,643
63		3	8	1,76	5,28	2,086
64		3	8	1,24	3,72	1,469
65		2	8	1,26	2,52	0,995
66		6	8	1,58	9,48	3,745
67		4	16	6,40	25,60	40,448
68		4	16	11,65	46,60	73,628
69		1	16	10,65	10,65	16,827
70		10	25	10,85	108,50	417,725
71		5	25	8,405	42,025	161,796

BIEGELISTE Stabstahl B500

















Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
72		1	16	3,50	3,50	5,530
73		1	16	4,85	4,85	7,663
74		6	16	7,10	42,60	67,308
75		6	25	12,00	72,00	277,200
76		4	16	7,20	28,80	45,504
77		7	20	8,60	60,20	148,694
78		4	16	4,15	16,60	26,228
79		1	16	7,40	7,40	11,692
80		12	12	1,30	15,60	13,853
81		136	12	2,10	285,60	253,613
82		262	10	1,10	288,20	177,819
83		24	8	0,88	21,12	8,342
84		60	20	3,10	186,00	459,420
85		14	16	1,60	22,40	35,392
86		3	16	10,05	30,15	47,637
87		4	16	8,45	33,80	53,404

BIEGELISTE Stabstahl B500

Projekt: Zentralklärwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
88		1	16	6,60	6,60	10,428
89		6	20	8,405	50,43	124,562
90		7	20	12,00	84,00	207,480
91		1	16	11,25	11,25	17,775
92		1	16	7,50	7,50	11,850
93		1	16	10,40	10,40	16,432
94		3	16	6,90	20,70	32,706
95		6	25	7,21	43,26	166,551
96		6	25	12,00	72,00	277,200
97		10	25	3,50	35,00	134,750
98		4	8	1,90	7,60	3,002
99		2	8	2,08	4,16	1,643
100		1	8	1,46	1,46	0,577
101		1	8	1,38	1,38	0,545

BIEGELISTE Stabstahl B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
102		2	8	1,44	2,88	1,138
103		166	10	2,92	484,72	299,072
104		58	10	3,12	180,96	111,652
105		28	10	2,88	80,64	49,755
106		57	10	3,08	175,56	108,321
107		10	8	1,76	17,60	6,952
108		4	16	2,13	8,52	13,462
109		2	16	2,46	4,92	7,774
110		2	8	1,55	3,10	1,225
111		2	8	1,84	3,68	1,454

BIEGELISTE Stabstahl B500











Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
112		2	8	1,88	3,76	1,485
113		2	8	1,68	3,36	1,327
114		2	8	1,82	3,64	1,438
115		3	16	2,26	6,78	10,712
116		6	16	2,05	12,30	19,434
117		160	8	1,75	280,00	110,600
118	LFDM 	1	8	1.760,00	1.760,00	695,200
119		6	20	2,83	16,98	41,941
120		3	20	2,90	8,70	21,489
121		9	25	3,43	30,87	118,850

BIEGELISTE Stabstahl B500










Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
122		1	8	2,02	2,02	0,798
123		1	8	1,92	1,92	0,758
124		1	8	1,52	1,52	0,600
125		72	8	3,38	243,36	96,127
126		88	10	3,16	278,08	171,575
127		99	8	3,34	330,66	130,611
128		28	8	3,12	87,36	34,507
129		48	12	3,40	163,20	144,922
130		3	12	3,22	9,66	8,578

BIEGELISTE Stabstahl B500










Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
131		48	12	2,98	143,04	127,020
132		8	10	3,16	25,28	15,598
133		13	8	2,84	36,92	14,583
134		13	8	3,04	39,52	15,610
135		6	12	2,96	17,76	15,771
136		6	10	2,12	12,72	7,848
137		13	10	1,88	24,44	15,079
138		13	10	1,40	18,20	11,229
139		7	10	2,08	14,56	8,984

BIEGELISTE Stabstahl B500

Projekt: Zentralklärwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plannr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
140		7	10	1,36	9,52	5,874
141		4	16	1,97	7,88	12,450
142		4	8	1,96	7,84	3,097
143		8	10	3,38	27,04	16,684
144		7	10	1,10	7,70	4,751
145		7	10	2,04	14,28	8,811
146		7	10	2,34	16,38	10,106
147		1	8	2,28	2,28	0,901
148		102	8	3,30	336,60	132,957

BIEGELISTE Stabstahl B500











Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Fundamente Maschinenhaus

Plan nr.: B06-02

Datum: 10.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
149		135	8	2,88	388,80	153,576
150		102	8	3,08	314,16	124,093
151		6	16	2,16	12,96	20,477
152		2	16	2,21	4,42	6,984
153		5	8	1,61	8,05	3,180
154		1	8	1,47	1,47	0,581
155		16	12	3,15	50,40	44,755
156		14	10	1,51	21,14	13,043
157		14	10	1,59	22,26	13,734
158		30	8	2,00	60,00	23,700

(Alle Angaben gerundet!)