

## RUNDSTAHL-STÜCKLISTE B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Balken im 1.OG und Stb. Attikabalken

Plannr.: B20-02

Datum: 05.04.2024

POS.	STÜCK	ø (mm)	SCHNITTLÄNGE (m)	GEWICHT (kg)	GESAMTLÄNGE (m)
1	16	10	1,210	0,747	19,360
2	414	8	0,740	0,292	306,360
3	6	14	12,000	14,520	72,000
4	26	10	12,000	7,404	312,000
5	12	10	1,270	0,784	15,240
6	6	14	7,500	9,075	45,000
7	26	10	6,850	4,226	178,100
8	16	14	1,850	2,239	29,600
9	240	8	1,580	0,624	379,200
10	240	8	2,000	0,790	480,000
11	16	8	1,750	0,691	28,000
12	20	8	0,740	0,292	14,800
13	180	8	2,940	1,161	529,200
14	6	12	6,250	5,550	37,500
15	116	8	0,860	0,340	99,760
16	4	20	7,650	18,896	30,600
17	6	20	4,000	9,880	24,000
18	16	12	1,370	1,217	21,920
19	3	12	1,710	1,518	5,130
20	16	12	10,000	8,880	160,000
21	4	10	10,000	6,170	40,000
22	4	14	1,770	2,142	7,080
23	6	20	10,900	26,923	65,400
24	4	20	6,800	16,796	27,200
25	16	12	4,000	3,552	64,000
26	4	10	3,900	2,406	15,600
27	8	20	2,200	5,434	17,600
28	28	8	1,300	0,514	36,400
29	4	20	8,850	21,860	35,400
30	6	12	6,400	5,683	38,400
31	4	10	10,000	6,170	40,000
32	4	20	5,600	13,832	22,400
33	6	12	7,750	6,882	46,500
34	4	10	3,900	2,406	15,600
35	6	12	1,710	1,518	10,260
36	4	14	7,200	8,712	28,800
37	4	14	2,450	2,965	9,800
38	12	14	1,510	1,827	18,120
39	4	14	5,100	6,171	20,400
40	95	8	0,660	0,261	62,700

## RUNDSTAHL-STÜCKLISTE B500

Projekt: Zentralklärwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Balken im 1.OG und Stb. Attikabalken

Plannr.: B20-02

Datum: 05.04.2024

### GESAMTMENGE (BETONSTAHL B500)

(mm)	(kg/m)	(m)	(kg)
8	0,395	1.936,420	764,886
10	0,617	635,900	392,350
12	0,888	383,710	340,734
14	1,210	230,800	279,268
20	2,470	222,600	549,822
GESAMTGEWICHT			2.327,060

(Alle Angaben gerundet!)

## BIEGELISTE Stabstahl B500













Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Balken im 1.OG und Stb. Attikabalken

Plannr.: B20-02

Datum: 05.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
1		16	10	1,21	19,36	11,945
2		414	8	0,74	306,36	121,012
3		6	14	12,00	72,00	87,120
4		26	10	12,00	312,00	192,504
5		12	10	1,27	15,24	9,403
6		6	14	7,50	45,00	54,450
7		26	10	6,85	178,10	109,888
8		16	14	1,85	29,60	35,816
9		240	8	1,58	379,20	149,784
10		240	8	2,00	480,00	189,600
11		16	8	1,75	28,00	11,060
12		20	8	0,74	14,80	5,846

## BIEGELISTE Stabstahl B500
















Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Balken im 1.OG und Stb. Attikabalken

Plannr.: B20-02

Datum: 05.04.2024

Pos.	Skizze [m/cm]	Stück	Ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
13		180	8	2,94	529,20	209,034
14		6	12	6,25	37,50	33,300
15		116	8	0,86	99,76	39,405
16		4	20	7,65	30,60	75,582
17		6	20	4,00	24,00	59,280
18		16	12	1,37	21,92	19,465
19		3	12	1,71	5,13	4,555
20		16	12	10,00	160,00	142,080
21		4	10	10,00	40,00	24,680
22		4	14	1,77	7,08	8,567
23		6	20	10,90	65,40	161,538
24		4	20	6,80	27,20	67,184
25		16	12	4,00	64,00	56,832
26		4	10	3,90	15,60	9,625
27		8	20	2,20	17,60	43,472

## BIEGELISTE Stabstahl B500














Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Balken im 1.OG und Stb. Attikabalken

Plannr.: B20-02

Datum: 05.04.2024

Pos.	Skizze [m/cm]	Stück	Ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
28		28	8	1,30	36,40	14,378
29		4	20	8,85	35,40	87,438
30		6	12	6,40	38,40	34,099
31		4	10	10,00	40,00	24,680
32		4	20	5,60	22,40	55,328
33		6	12	7,75	46,50	41,292
34		4	10	3,90	15,60	9,625
35		6	12	1,71	10,26	9,111
36		4	14	7,20	28,80	34,848
37		4	14	2,45	9,80	11,858
38		12	14	1,51	18,12	21,925
39		4	14	5,10	20,40	24,684
40		95	8	0,66	62,70	24,767

(Alle Angaben gerundet!)