

RUNDSTAHL - STÜCKLISTE B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Bewehrung Stützen EG - Teil 1

Plannr.: B15-01

Datum: 03.04.2024

POS.	STÜCK	ø (mm)	SCHNITTLÄNGE (m)	GEWICHT (kg)	GESAMTLÄNGE (m)
1	4	14	1,800	2,178	7,200
2	3	14	5,100	6,171	15,300
3	3	14	5,100	6,171	15,300
4	36	20	5,500	13,585	198,000
5	34	8	1,820	0,719	61,880
6	18	8	1,100	0,435	19,800
7	12	8	1,700	0,672	20,400
8	4	12	1,900	1,687	7,600
9	6	8	1,000	0,395	6,000
10	2	12	1,200	1,066	2,400
11	34	8	1,840	0,727	62,560
12	18	8	1,100	0,435	19,800
13	34	8	1,880	0,743	63,920
14	18	8	1,100	0,435	19,800
15	64	8	1,380	0,545	88,320
16	34	8	0,920	0,363	31,280
17	4	20	5,250	12,968	21,000
18	32	8	0,980	0,387	31,360
19	12	14	4,750	5,748	57,000
20	4	20	5,450	13,462	21,800
21	32	8	3,000	1,185	96,000
22	17	8	1,760	0,695	29,920
23	17	8	1,040	0,411	17,680
24	4	14	4,400	5,324	17,600
25	33	8	1,180	0,466	38,940

GESAMTMENGE (BETONSTAHL B500)

(mm)	(kg/m)	(m)	(kg)
8	0,395	607,660	240,025
12	0,888	10,000	8,880
14	1,210	112,400	136,004
20	2,470	240,800	594,776

GESAMTGEWICHT

979,685

(Alle Angaben gerundet!)

BIEGELISTE Stabstahl B500














Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Bewehrung Stützen EG - Teil 1

Plannr.: B15-01

Datum: 03.04.2024

Pos.	Skizze [m/cm]	Stück	Ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
1		4	14	1,80	7,20	8,712
2		3	14	5,10	15,30	18,513
3		3	14	5,10	15,30	18,513
4		36	20	5,50	198,00	489,060
5		34	8	1,82	61,88	24,443
6		18	8	1,10	19,80	7,821
7		12	8	1,70	20,40	8,058
8		4	12	1,90	7,60	6,749
9		6	8	1,00	6,00	2,370
10		2	12	1,20	2,40	2,131
11		34	8	1,84	62,56	24,711
12		18	8	1,10	19,80	7,821
13		34	8	1,88	63,92	25,248

BIEGELISTE Stabstahl B500











Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Bewehrung Stützen EG - Teil 1

Plannr.: B15-01

Datum: 03.04.2024

Pos.	Skizze [m/cm]	Stück	ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
14		18	8	1,10	19,80	7,821
15		64	8	1,38	88,32	34,886
16		34	8	0,92	31,28	12,356
17		4	20	5,25	21,00	51,870
18		32	8	0,98	31,36	12,387
19		12	14	4,75	57,00	68,970
20		4	20	5,45	21,80	53,846
21		32	8	3,00	96,00	37,920
22		17	8	1,76	29,92	11,818
23		17	8	1,04	17,68	6,984

BIEGELISTE Stabstahl B500



Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Bewehrung Stützen EG - Teil 1

Plannr.: B15-01

Datum: 03.04.2024

Pos.	Skizze [m/cm]	Stück	ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
24		4	14	4,40	17,60	21,296
25		33	8	1,18	38,94	15,381