

RUNDSTAHL - STÜCKLISTE B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Bewehrung Stützen 1.OG - Teil 2

Plannr.: B19-01

Datum: 05.04.2024

| POS. | STÜCK | ø (mm) | SCHNITTLÄNGE (m) | GEWICHT (kg) | GESAMTLÄNGE (m) |
|-------------------------------|-------|-----------|---------------------|-----------------|--------------------|
| 1 | 20 | 20 | 3,300 | 8,151 | 66,000 |
| 2 | 12 | 10 | 1,500 | 0,925 | 18,000 |
| 3 | 20 | 8 | 0,740 | 0,292 | 14,800 |
| 4 | 132 | 8 | 0,980 | 0,387 | 129,360 |
| 5 | 26 | 8 | 1,380 | 0,545 | 35,880 |
| 6 | 14 | 8 | 0,920 | 0,363 | 12,880 |
| 7 | 56 | 12 | 3,100 | 2,753 | 173,600 |
| 8 | 52 | 8 | 3,060 | 1,209 | 159,120 |
| 9 | 26 | 8 | 1,280 | 0,506 | 33,280 |
| 10 | 32 | 8 | 0,840 | 0,332 | 26,880 |
| 11 | 12 | 20 | 4,350 | 10,745 | 52,200 |
| 12 | 33 | 8 | 1,180 | 0,466 | 38,940 |
| 13 | 4 | 20 | 4,250 | 10,498 | 17,000 |
| 14 | 12 | 12 | 4,250 | 3,774 | 51,000 |
| 15 | 31 | 8 | 2,980 | 1,177 | 92,380 |
| 16 | 17 | 8 | 1,480 | 0,585 | 25,160 |
| 17 | 4 | 10 | 1,750 | 1,080 | 7,000 |
| GESAMTMENGE (BETONSTAHL B500) | | | | | |
| | (mm) | (kg/m) | (m) | (kg) | |
| | 8 | 0,395 | 568,680 | 224,629 | |
| | 10 | 0,617 | 25,000 | 15,425 | |
| | 12 | 0,888 | 224,600 | 199,445 | |
| | 20 | 2,470 | 135,200 | 333,944 | |
| GESAMTGEWICHT | | | | | 773,443 |

(Alle Angaben gerundet!)

BIEGELISTE Stabstahl B500












Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Bewehrung Stützen 1.OG - Teil 2

Plannr.: B19-01

Datum: 05.04.2024

| Pos. | Skizze [m/cm] | Stück | ∅ | Schnittlänge [m] | Gesamtlänge [m] | Pos.-Gewicht [kg] |
|------|---|-------|----|---------------------|--------------------|----------------------|
| 1 |  | 20 | 20 | 3,30 | 66,00 | 163,020 |
| 2 |  | 12 | 10 | 1,50 | 18,00 | 11,106 |
| 3 |  | 20 | 8 | 0,74 | 14,80 | 5,846 |
| 4 |  | 132 | 8 | 0,98 | 129,36 | 51,097 |
| 5 |  | 26 | 8 | 1,38 | 35,88 | 14,173 |
| 6 |  | 14 | 8 | 0,92 | 12,88 | 5,088 |
| 7 |  | 56 | 12 | 3,10 | 173,60 | 154,157 |
| 8 |  | 52 | 8 | 3,06 | 159,12 | 62,852 |
| 9 |  | 26 | 8 | 1,28 | 33,28 | 13,146 |
| 10 |  | 32 | 8 | 0,84 | 26,88 | 10,618 |
| 11 |  | 12 | 20 | 4,35 | 52,20 | 128,934 |

BIEGELISTE Stabstahl B500







Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Bewehrung Stützen 1.OG - Teil 2

Plannr.: B19-01

Datum: 05.04.2024

| Pos. | Skizze [m/cm] | Stück | Ø | Schnittlänge [m] | Gesamtlänge [m] | Pos.-Gewicht [kg] |
|------|---|-------|----|---------------------|--------------------|----------------------|
| 12 |  | 33 | 8 | 1,18 | 38,94 | 15,381 |
| 13 |  | 4 | 20 | 4,25 | 17,00 | 41,990 |
| 14 |  | 12 | 12 | 4,25 | 51,00 | 45,288 |
| 15 |  | 31 | 8 | 2,98 | 92,38 | 36,490 |
| 16 |  | 17 | 8 | 1,48 | 25,16 | 9,938 |
| 17 |  | 4 | 10 | 1,75 | 7,00 | 4,319 |