

RUNDSTAHL - STÜCKLISTE B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Wände 1.OG bis DG Maschinenhaus

Plannr.: B10-02

Datum: 11.04.2024

POS.	STÜCK	ø (mm)	SCHNITTLÄNGE (m)	GEWICHT (kg)	GESAMTLÄNGE (m)
1	8	10	1,860	1,148	14,880
2	8	10	2,860	1,765	22,880
3	22	10	2,260	1,394	49,720
4	4	12	4,000	3,552	16,000
5	556	10	3,300	2,036	1.834,800
6	16	10	2,700	1,666	43,200
7	30	10	1,750	1,080	52,500
8	28	12	2,200	1,954	61,600
9	14	10	2,600	1,604	36,400
10	59	10	1,260	0,777	74,340
11	15	10	2,060	1,271	30,900
12	4	12	1,300	1,154	5,200
13	4	12	2,800	2,486	11,200
14	186	10	3,650	2,252	678,900
15	7	10	3,060	1,888	21,420
16	15	10	3,360	2,073	50,400
17	9	12	1,380	1,225	12,420
18	20	12	2,150	1,909	43,000
19	182	12	6,100	5,417	1.110,200
20	88	12	4,900	4,351	431,200
21	45	12	1,780	1,581	80,100
22	72	12	4,700	4,174	338,400
23	16	12	2,350	2,087	37,600
24	46	12	1,320	1,172	60,720
25	18	12	3,350	2,975	60,300
26	91	12	1,390	1,234	126,490
27	455	12	1,690	1,501	768,950
28	14	10	1,900	1,172	26,600
29	14	10	3,100	1,913	43,400
30	48	12	3,400	3,019	163,200
31	16	12	3,700	3,286	59,200
32	364	10	2,500	1,543	910,000
33	730	8	0,410	0,162	299,300
34	182	10	1,690	1,043	307,580
GESAMTMENGE (BETONSTAHL B500)					
	(mm)	(kg/m)		(m)	(kg)
	8	0,395		299,300	118,224

RUNDSTAHL - STÜCKLISTE B500

Projekt: Zentralklärwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Wände 1.OG bis DG Maschinenhaus

Plannr.: B10-02

Datum: 11.04.2024

GESAMTMENGE (BETONSTAHL B500)

(mm)	(kg/m)	(m)	(kg)
10	0,617	4.197,920	2.590,116
12	0,888	3.385,780	3.006,575
GESAMTGEWICHT			5.714,915

(Alle Angaben gerundet!)

BIEGELISTE Stabstahl B500

















Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Wände 1.OG bis DG Maschinenhaus

Plannr.: B10-02

Datum: 11.04.2024

Pos.	Skizze [m/cm]	Stück	Ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
1		8	10	1,86	14,88	9,181
2		8	10	2,86	22,88	14,117
3		22	10	2,26	49,72	30,677
4		4	12	4,00	16,00	14,208
5		556	10	3,30	1.834,80	1.132,072
6		16	10	2,70	43,20	26,654
7		30	10	1,75	52,50	32,392
8		28	12	2,20	61,60	54,701
9		14	10	2,60	36,40	22,459
10		59	10	1,26	74,34	45,868
11		15	10	2,06	30,90	19,065
12		4	12	1,30	5,20	4,618
13		4	12	2,80	11,20	9,946
14		186	10	3,65	678,90	418,881
15		7	10	3,06	21,42	13,216
16		15	10	3,36	50,40	31,097

BIEGELISTE Stabstahl B500














Projekt: Zentralklärwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Wände 1.OG bis DG Maschinenhaus

Plannr.: B10-02

Datum: 11.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
17		9	12	1,38	12,42	11,029
18		20	12	2,15	43,00	38,184
19		182	12	6,10	1.110,20	985,858
20		88	12	4,90	431,20	382,906
21		45	12	1,78	80,10	71,129
22		72	12	4,70	338,40	300,499
23		16	12	2,35	37,60	33,389
24		46	12	1,32	60,72	53,919
25		18	12	3,35	60,30	53,546
26		91	12	1,39	126,49	112,323
27		455	12	1,69	768,95	682,828
28		14	10	1,90	26,60	16,412
29		14	10	3,10	43,40	26,778

BIEGELISTE Stabstahl B500






Projekt: Zentralklärwerk Westerland Sylt

Bauwerk: Maschinenhaus

Bauteil: Wände 1.OG bis DG Maschinenhaus

Plannr.: B10-02

Datum: 11.04.2024

Pos.	Skizze [m/cm]	Stück	ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
30		48	12	3,40	163,20	144,922
31		16	12	3,70	59,20	52,570
32		364	10	2,50	910,00	561,470
33		730	8	0,41	299,30	118,224
34		182	10	1,69	307,58	189,777