

RUNDSTAHL - STÜCKLISTE B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Bewehrung Stützen EG - Teil 2

Plannr.: B16-01

Datum: 03.04.2024

POS.	STÜCK	ø (mm)	SCHNITTLÄNGE (m)	GEWICHT (kg)	GESAMTLÄNGE (m)
2	90	8	0,980	0,387	88,200
4	39	8	1,380	0,545	53,820
5	20	8	0,920	0,363	18,400
8	78	8	3,060	1,209	238,680
11	46	8	1,280	0,506	58,880
13	34	8	1,180	0,466	40,120
14	2	12	1,500	1,332	3,000
15	6	8	1,300	0,514	7,800
17	3	12	1,600	1,421	4,800
18	9	8	1,400	0,553	12,600
19	12	12	4,950	4,396	59,400
20	4	20	5,500	13,585	22,000
21	34	8	2,980	1,177	101,320
22	18	8	1,480	0,585	26,640
23	12	8	1,000	0,395	12,000
24	4	12	1,200	1,066	4,800
25	4	14	1,800	2,178	7,200
28	20	20	6,250	15,438	125,000
29	56	12	5,750	5,106	322,000
30	84	8	0,980	0,387	82,320
31	24	8	0,900	0,356	21,600
32	8	20	5,500	13,585	44,000
33	18	8	0,840	0,332	15,120
34	4	20	5,450	13,462	21,800

GESAMTMENGE (BETONSTAHL B500)
(mm) (kg/m)

		(m)	(kg)
8	0,395	777,500	307,112
12	0,888	394,000	349,871
14	1,210	7,200	8,712
20	2,470	212,800	525,616

GESAMTGEWICHT 1.191,311

(Alle Angaben gerundet!)

BIEGELISTE Stabstahl B500











Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Bewehrung Stützen EG - Teil 2

Plannr.: B16-01

Datum: 03.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
2		90	8	0,98	88,20	34,839
4		39	8	1,38	53,82	21,259
5		20	8	0,92	18,40	7,268
8		78	8	3,06	238,68	94,279
11		46	8	1,28	58,88	23,258
13		34	8	1,18	40,12	15,847
14		2	12	1,50	3,00	2,664
15		6	8	1,30	7,80	3,081
17		3	12	1,60	4,80	4,262
18		9	8	1,40	12,60	4,977

BIEGELISTE Stabstahl B500

Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Bewehrung Stützen EG - Teil 2

Plannr.: B16-01

Datum: 03.04.2024

Pos.	Skizze [m/cm]	Stück	∅	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
19		12	12	4,95	59,40	52,747
20		4	20	5,50	22,00	54,340
21		34	8	2,98	101,32	40,021
22		18	8	1,48	26,64	10,523
23		12	8	1,00	12,00	4,740
24		4	12	1,20	4,80	4,262
25		4	14	1,80	7,20	8,712
28		20	20	6,25	125,00	308,750
29		56	12	5,75	322,00	285,936
30		84	8	0,98	82,32	32,516
31		24	8	0,90	21,60	8,532
32		8	20	5,50	44,00	108,680

BIEGELISTE Stabstahl B500



Projekt: Zentralkläwerk Westerland Sylt

Bauwerk: Entwässerungsgebäude

Bauteil: Bewehrung Stützen EG - Teil 2

Plannr.: B16-01

Datum: 03.04.2024

Pos.	Skizze [m/cm]	Stück	Ø	Schnittlänge [m]	Gesamtlänge [m]	Pos.-Gewicht [kg]
33		18	8	0,84	15,12	5,972
34		4	20	5,45	21,80	53,846